# ज़ाकिर हुसैन दिल्ली कॉलेज (सांध्य)

## Zakir Husain Delhi College (Evening)

दिल्ली विश्वविद्यालय (University of Delhi)

जवाहरलाल नेहरू मार्ग, नई दिल्ली - ११०००२ Jawaharlal Nehru Marg, New Delhi – 110002

Phone: 011-23231899 Website: https://zhdce.ac.in/ E-mail: zhpge.college@gmail.com, principal@zhe.du.ac.in


**'NAAC ACCREDITED'**

Ref: ZHDCE/Quotation/2026/2 1-10-2026

## NOTICE INVITING QUOTATIONS

Sealed quotations are invited from the reputed contractors for the following works of the college:

**Name of Project : Repair and Renovation of the Computer Lab**

| Sl. No. | Description | Qty | Unit | Rate | Amount |
|---|---|---|---|---|---|
| 1. | Dismantling tile work in Walls/floors/roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 8mm to 15mm | 360 | Sqft | | |
| 2. | 15 mm cement plaster on rough side of single or half brick wall of mix: 1:4 (1 cement: 2 coarse sand:2 Fine Sand) | 360 | Sqft | | |
| 3. | Providing and applying white cement based putty of average thickness 1mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. | 1 | Job | | |
| 4. | Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. Two or more coats | 1 | Job | | |
| 5. | Disposal of building rubbish/malba/ unserviceable material by mechanical means, including loading, transporting and unloading at approved municipal dumping ground, beyond 50 m initial lead, for all leads and lifts. | 1 | Job | | |
| 6. | Creation of Electrical Points for each workstation area. The workstation would have electrical points & UPS points (Wires-Finolex/Havells: Conduits-AKG/Polypack: Switch/Socket/Cover Plate-Legrand, Schneider, Anchor or equivalent) from existing | 729 | Sqft | | |

ज़ाकिर हुसैन दिल्ली कॉलेज (सांध्य)
Zakir Husain Delhi College (Evening)
दिल्ली विश्वविद्यालय (University of Delhi)
जवाहरलाल नेहरू मार्ग, नई दिल्ली - ११०००२ Jawaharlal Nehru Marg, New Delhi – 110002
Phone: 011-23231899 Website: https://zhdce.ac.in/ E-mail: zhpge.college@gmail.com, principal@zhe.du.ac.in

'NAAC ACCREDITED'

| | | | | | |
|---|---|---|---|---|---|
| | Distribution board/Electric panel area and the existing electric connections routing the conduits & cables through the false ceiling with proper connection, commissioning & testing. | | | | |
| 7. | Creation of LAN Points for each workstation area. The workstation would have data points, (Wires Finolex/ Havells / D-Link: Conduits /AKG/ Polypack: IO/RJ-45, Cover plate- D-Link/Legrand/Anchor or equivalent) from server area and the existing EPABX connections routing the conduits & cables through the false ceiling with proper connection & commissioning & testing. | 56.00 | Nos | | |
| 8. | Providing provision of placing in position Sound system & HDMI including the cost of wiring, conduits, connecting plates etc complete. | 1.00 | Job | | |
| 9. | Providing & fixing wooden flush Door 35mm thick including the cost of all the required fittings, sunmica /polish etc. complete. | 2.00 | Nos | | |
| | Total | | | | |

Terms and Conditions :

1. Your rates must be quoted with GST and other relevant taxes as applicable.
2. You have to complete the work order with two weeks of work order.
3. The quantities may vary at the time of placing the work order.
4. The payment shall be made as per the actual work done on site.
5. The quotation envelop should be sealed and super-scribed with the name of the project.
6. Your rates shall be valid for six months from the date of submission of quotation.
7. The undersigned has a right to accept or reject any item and rates partially or fully.
8. **Please send your rates by post on the college address or by hand on or before 23-10-2026.**

Prof. Bharat Singh
Principal / OSD