ज़ाकिर हुसैन दिल्ली कॉलेज (सांध्य)

Zakir Husain Delhi College (Evening)

दिल्ली विश्वविद्यालय (University of Delhi)

जवाहरलाल नेहरू मार्ग, नई दिल्ली - ११०००२ Jawaharlal Nehru Marg, New Delhi – 110002

Phone: 011-23231899 Website: https://zhdce.ac.in/ E-mail: zhpge.college@gmail.com, principal@zhe.du.ac.in

'NAAC ACCREDITED'

Ref: ZHDCE/Quotation/2026/1

9-09-2026

NOTICE INVITING QUOTATIONS

Sealed quotations are invited from the reputed contractors for the following works of the college:

Name of Project : False Ceiling and allied works of the Computer Lab – 1

Sl. No.	Description	Qty	Unit	Rate	Amount
1.	Dismantling Aluminum/ Gypsum/Grid False Ceiling/Partition including disposal of unserviceable material and stacking of serviceable material within 50 meters lead as directed by college authorities.	69.00	Sqm		
2.	Creation of Electrical Points for Air Conditioners in lab area (Wires- Finolex/ Havells : Conduits- AKG/ Polypack: Switch/ Socket/Cover Plate- Legrand, Schneider, Anchor or equivalent) from existing Distribution board/Electric panel and making the electric connections routing through the conduits & cables through the false ceiling with proper connection, commissioning & testing.	2.00	Sqft		
3.	S/F/I/Testing and commissioning of pre wired LED 2'x2' false ceiling type fitting 40W/45W complete with all accessories and P/F suitable hanging arrangement including connection with 1.5sqmm FRLS PVC Copper conductor cable in suitable size PVC sleeve etc as required (Philips/Wipro/Crompton or equivalent make)	12.00	Nos		
4.	Providing and fixing false ceiling at all heights with integral densified calcium silicate reinforced with fiber and natural filler false ceiling tiles of Size 595x595 mm of approved texture, design and patterns , Light reflectance of 85% (minimum). Non-combustible as per BS:476(part-4), fire performance as per BS:476 (part 6 &7), humidity resistance of 100%, thermal conductivity < 0.043 W/m K as per ASTM 518:1991, in true horizontal level suspended on inter-locking metal powder coated T-Grid of hot dipped galvanized iron section of 0.40 mm thick on Silhouette profile	69.00	Job		

ज़ाकिर हुसैन दिल्ली कॉलेज (सांध्य)

Zakir Husain Delhi College (Evening)

दिल्ली विश्वविद्यालय (University of Delhi)

जवाहरलाल नेहरू मार्ग, नई दिल्ली - ११०००२ Jawaharlal Nehru Marg, New Delhi – 110002

Phone: 011-23231899 Website: https://zhdce.ac.in/ E-mail: zhpge.college@gmail.com, principal@zhe.du.ac.in

'NAAC ACCREDITED'

	,rotary stitched double webbed white with 6 mm reveal profile (white/black),comprising of main-T runners of size 15x42 mm of length 3000mm, cross - T of size 15x42 mm of length 1200 mm and second ary intermediate cross-T of size 15x42 mm of length 600 mm to form grid module of size 600 x 600 mm, suspended from ceiling using galvanized mild steel items.				
5.	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	1.00	Job		
6.	Providing and applying white cement based putty of average thickness 1mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	1.00	Job		
7.	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ liter, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. Two or more coats	1.00	Job		

Terms and conditions :

1. Your rates must be quoted with GST and other relevant taxes as applicable.
2. You have to complete the work order with two weeks of work order.
3. The quantities may vary at the time of placing the work order.
4. The payment shall be made as per the actual work done on site.
5. The quotation envelop should be sealed and super-scribed with the name of the project.
6. Your rates shall be valid for six months from the date of submission of quotation.
7. The undersigned has a right to accept or reject any item and rates partially or fully.
8. **Please send your rates by post on the college address or by hand on or before 30-09-2026.**

09/9/26

Prof. Bharat Singh
Principal / OSD